

#### QUALIFICATION TEST REPORT

AMP\* Ultra-Fast Plus Fully Insulated FASTON\* Receptacle Terminals

501-62

Rev. A

Product Specification:

CTL Numbers:

108-2044, Rev. A

CTL1117-301-005. CTL1117-020

CTL1117-038-021

Date:

05/03/89

Classification:

Unrestricted

Prepared By:

Daniel E. McCLure

Revised:

James D'Angelo Per ECN B-5854

\*Trademark of AMP Incorporated

## Table of Contents

1. 1 1. 2 1. 3 1. 4 1. 5	Introduction Purpose Scope Conclusions Product Description Test Samples Qualification Test Sequence	Page Page	1 1 1 2 2 3
2. 1 2. 2 2. 3 2. 4 2. 5 2. 6 2. 7 2. 8 2. 9 2.10 2.11 2.12 2.13 2.14	Summary of Testing.  Examination of Product  Dielectric Withstanding, Test Condition A  Dielectric Withstanding, Test Condition C  Dielectric Withstanding, Tab Recep. Entry Position.  Heating (T-Rise)  Heat Cycling (Current Cycling)  Pull Out (Wire Crimp Tensile)  Pull Out (Insulation Crimp Tensile)  Secureness of Insulation (Unassembled)  Secureness of Insulation (Assembled)  Engagement & Disengagement  Flex Insulation Crimp  Heat Age, 136°C  Heat Age, Humidity	Page Page Page Page Page Page Page Page	4 4 4 4 4 5 6 6 7 7 7 8 8 8
3. 1 3. 2 3. 3 3. 4 3. 5 3. 6 3. 7 3. 8 3. 9 3.10 3.11 3.12 3.13 3.14	Test Methods.  Examination of Product  Dielectric Withstanding, Test Condition A  Dielectric Withstanding, Test Condition C  Dielectric Withstanding, Tab Recep. Entry Position.  Heating (T-Rise)  Heat Cycling (Current Cycling)  Pull Out (Wire Crimp Tensile)  Pull Out (Insulation Crimp Tensile)  Secureness of Insulation (Unassembled)  Secureness of Insulation (Assembled)  Engagement & Disengagement  Flex Insulation Crimp  Heat Age, 136°C  Heat Age, Humidity	Page Page Page Page Page Page Page Page	10 10 10 10 11 11
4.	Validation	Page	12



### AMP INCORPORATED

HARRISBURG, PENNSYLVANIA 17105 PHONE: 717-564-0100 TWX: 510-657-4110

#### CORPORATE TEST LABORATORY

Qualification Test Report on AMP Ultra-Fast Plus Fully Insulated FASTON Receptacle Terminals

AMP P/N 2-520401-2, 3-520402-2, 2-520405-2, 3-520406-2, 2-520932-2

#### 1. Introduction

#### 1.1 Purpose

Testing was performed on AMP Ultra-Fast Plus Fully Insulated FASTON Receptacle Terminals to determine if they meet the performance requirements of AMP Product Specification 108-2044, Rev. A.

#### 1.2 Scope

This report covers the electrical, mechanical and environmental performance of the Ultra-Fast Fully Insulated FASTON Receptacle Terminals, manufactured by the Automotive/Consumers Business Group. Testing on the Series 187 and 250 Receptacles was performed between April 16, 1985 and November 18,1987. Testing on the Series 110 Receptacles was performed between February 13, 1989 and April 21, 1989.

#### 1.3 Conclusions

The Ultra-Fast Plus Fully Insulated FASTON Receptacle Terminals meet the electrical, mechanical and environmental performance requirements of AMP Product Specification 108-2044, Rev. A.

#### 1.4 Product Description

AMP Ultra-Fast Plus Fully Insulated FASTON Receptacle Terminals mate with FASTON tabs, which are used in appliances and other commercial equipment. The tin plated copper alloy FASTON terminal is completely enclosed in a Nylon housing. Assemblies are color coded by wire size, and terminated on solid, fused, or stranded wire ranging from AWG 22 thru AWG 14.

### 1.5 <u>Test Samples</u>

The samples were taken randomly from current production, and all samples tested were receptacles. The following sample quantities were used for each test group:

Test Groups	Quantity	Part Number	Wire Sizes	Description
1,2,3,4,12	60	2-520401-2	22,20,18	187 Series
	40	3-520402-2	16,14	187 Series
	60	2-520405-2	22,20,18	250 Series
	40	3-520406-2	16,14	250 Series
1,2	60	2-520932-2	22,20,18	110 Series
12	55	2-520932-2	22,18	110 Series
6,8,10,11	20	2-520401-2	22	187 Series
	20	3-520402-2	16	187 Series
	20	2-520405-2	22	250 Series
	20	3-520406-2	16	250 Series
8,10,11	20	2-520932-2	22	110 Series
5,7,9,13	20	2-520401-2	Unwired	187 Series
	20	3-520402-2	Unwired	187 Series
	20	2-520405-2	Unwired	250 Series
	20	3-520406-2	Unwired	250 Series
7,9,13	20	2-520932-2	Unwired	110 Series

#### 1.6 Test Sequence

	11					т	est (	Grou	<u>α</u>				
Test or Examination	1 1	2	3	4	5	6	7	8	9	10	11	12	13
rost of Examination	╫╌			<u>.                                    </u>	l		Seq	uenc	e (a)	l			
Examination of Product	1	1	1	1	1	1	1	1	1	1	1	1	1
Dielectric Withstand, Test Condition A		2	3	3 (b)	_								
Dielectric Withstand, Test Condition C					2								
Dielectric Withstand, Tab Receptacle Entry Position						2							
Heating (T-Rise)	2 <sub>(c)</sub>												
Heat Cycling (Current Cycle)	3 <sub>(c)</sub>				<u>.</u>								ļ <u> </u>
Pull Out (Crimp Tensile)		4					L.						
Pull Out (Insulation Crimp Tensile)												2	
Secureness of Insulation (Unassembled)							2		3				
Secureness of Insulation (Assembled)								2		3	3(b)		
Engagement & Disengagement												<u> </u>	2
Flex Insulation Crimp		3											
Heat Age, 136 ° C			2						2	2			
Heat Age, Humidity			T	2							2		

#### Figure 1

- (a) Number indicates sequence in which tests are performed.
- (b) Uncrimped terminals and wires in Test Groups 4 and 11 were conditioned in the environments indicated. After conditioning, each sample was crimped to an appropriate wire, and the electrical or mechanical test was performed.
- (c) Temperature rise and voltage drop measurements, during current cycling, were collected simultaneously. Samples were prepared, in accordance with Figure 3. Thermocouples must have strain relief suitable to protect interface.

#### 2. Summary of Testing

### 2.1 Examination of Product - Groups 1-14

All connectors submitted for testing were selected from production lots that were subjected to inspection and found to be acceptable by the Product Assurance Department of Automotive/Consumers Business Group.

## 2.2 Dielectric Withstanding, Test Condition A - Groups 2, 3, and 4

There was no dielectric breakdown or flashover on any sample, when a test voltage of 3.4 kv ac was applied for a one-minute hold period.

### 2.3 Dielectric Withstanding, Test Condition C - Group 5

There was no dielectric breakdown or flashover on any sample, when the test voltage of 3.0 kv ac was applied for a one-minute hold period.

# 2.4 Dielectric Withstanding, Tab Receptacle Entry Position - Group 6

There was no dielectric breakdown or flashover on any sample, when the test voltage of  $1.0\ kv$  ac was applied for a one-minute hold period.

## 2.5 Heating (Temperature Rise) - Group 1

All terminals tested met the specification requirement of 20°C or less temperature rise above ambient temperature.

All Temperatures are in Degrees C

Part No.	Temp.	Rise	Crimp	Wire	Specified	Ambient
	Max.	Avg.	Height*	Size	Current**	Temp.
2-520401-2 2-520401-2 3-520402-2 3-520402-2 3-520402-2 2-520405-2 2-520405-2 2-520406-2 3-520406-2 3-520406-2 2-520932-2 2-520932-2 2-520932-2	11.2 14.6 7.0 4.3 7.9 13.1 1.4 1.9 4.9 6.4 10.7 2.2 1.9 0.9	10.5 13.5 5.4 3.8 7.3 12.5 1.2 1.7 4.5 5.9 9.6 2.0 1.7	.065 .065 .070 .075 .075 .080 .065 .070 .075 .080 .065	22 20 18 18 16 14 22 20 18 16 14 22 20 18	6 8 14 14 20 30 6 8 14 20 30 6 8	26.1 26.1 25.1 26.2 26.2 27.1 26.2 25.9 26.3 26.2 26.7 24.6 24.9 25.7

<sup>\*</sup>Measurements are in inches

<sup>\*\*</sup>Direct Current

# 2.6 <u>Heat Cycling (Current Cycling) - Group 1</u>

All terminals tested met the specification requirement of  $65^{\circ}\text{C}$  or less temperature rise above ambient. All voltage drop measurements were less than the specification requirement.

#### 24th Cycle

Part	Wire	Test	Temp.	Rise**	Milliv	olts#	Spec.
Number	Size	Curr.*	Max.	Mean	Max.	Mean	Requirement
2-520401-2 2-520401-2 2-520401-2 3-520402-2 3-520402-2 3-520405-2 2-520405-2 2-520406-2 3-520406-2 3-520406-2 2-520932-2 2-520932-2 2-520932-2	22 20 18 18 16 14 22 20 18 16 14 22 20 18	6 8 14 14 20 30 6 8 14 20 30 4 6 8	6.2 10.0 20.0 17.4 29.9 51.6 5.4 7.4 16.3 29.5 38.5 3.1 5.5 8.0	5.6 8.6 18.2 16.7 28.1 46.3 4.7 6.5 14.9 26.6 36.9 2.6 4.9 7.6	4.88 5.98 13.75 9.66 11.97 19.81 4.49 4.79 7.66 9.71 14.76 5.43 5.19 6.03	3.98 4.91 11.75 8.79 10.99 18.73 3.13 4.21 6.99 9.02 13.32 4.04 4.63 5.16	14 mv 15 mv 17 mv 17 mv 19 mv 21 mv 10 mv 11 mv 13 mv 15 mv 20 mv 14 mv 15 mv 17 mv

<sup>\*</sup>Direct Current

#Crimp MVD + Friction MVD - E.W.L. = Millivolt Drop

### 500th Cycle

Part	Wire	Test	Temp.	Rise**	Milliv	olts#	Spec.
,	Size	Curr.*	Max.	Mean	Max.	Mean	Requirement
Number	3126	Cuir	- IIux -	TIC UII			
2-520401-2 2-520401-2 2-520401-2 3-520402-2 3-520402-2	22 20 18 18 16	6 8 14 14 20 30	5.8 8.8 20.0 20.5 28.8 50.0	5.4 7.9 17.7 19.7 27.6	4.71 6.29 19.11 10.33 13.05 19.84	4.38 5.46 10.92 9.18 12.30	18 mv 19 mv 21 mv 21 mv 23 mv 25 mv
3-520402-2	14		6.0	5.4	5.46	3.72	14 mv
2-520405-2	22	6	•				15 mv
2-520405-2	20	8	7.8	7.0	5.08	4.50	= <u>-</u>
2-520405-2	18	14	15.3	14.2	7.50	6.89	17 mv
3-520406-2	16	20	24.7	23.1	9.41	8.77	19 mv
3-520406-2	14	30	40.8	37.7	16.13	14.07	26 mv
2-520932-2	22	4	3.6	2.8	5.31	4.14	18 mv
2-520932-2	20	6	6.4	5.6	5.62	4.84	19 mv
2-520932-2	18	8	10.9	8.4	6.35	5.27	21 mv

<sup>\*</sup>Direct Current

#Crimp MVD + Friction MVD - E.W.L. = Millivolt Drop

<sup>\*\*</sup>Degrees C

<sup>\*\*</sup>Degrees C

# 2.7 Pull Out (Wire Crimp Tensile) - Group 2

All samples met the minimum specified requirements for Pull Out (Wire Crimp Tensile), in accordance with the specification.

Tensile in Pounds

	Max.	Mean	Crimp Ht.	AWG	Min.	кеq.
18.0 27.0 42.8 49.5 95.0 35.0 18.7 22.2 40.0 62.3	27.0 32.0 48.7 64.7 100 42.4 26.0 28.7 49.0 71.7	22.85 29.14 45.19 54.72 98.51 39.36 22.09 26.47 44.11 66.35	.065" .065" .070" .075" .080" .075" .065" .065"	22 20 18 16 14 18 22 20 18 16	10 16 20 30 60 20 10 16 20 30	lbs. lbs. lbs. lbs. lbs. lbs. lbs. lbs.
13.5 22.7	21.7	17.93 27.00	.065" .065"	22 20 18	10 16 20	lbs. lbs. lbs.
	27.0 42.8 49.5 95.0 35.0 18.7 22.2 40.0 62.3 101 13.5	27.0 32.0 42.8 48.7 49.5 64.7 95.0 100 35.0 42.4 18.7 26.0 22.2 28.7 40.0 49.0 62.3 71.7 101 111 13.5 21.7 22.7 30.0	27.0 32.0 29.14 42.8 48.7 45.19 49.5 64.7 54.72 95.0 100 98.51 35.0 42.4 39.36 18.7 26.0 22.09 22.2 28.7 26.47 40.0 49.0 44.11 62.3 71.7 66.35 101 111 107.5 13.5 21.7 17.93 22.7 30.0 27.00	27.0 32.0 29.14 .065" 42.8 48.7 45.19 .070" 49.5 64.7 54.72 .075" 95.0 100 98.51 .080" 35.0 42.4 39.36 .075" 18.7 26.0 22.09 .065" 22.2 28.7 26.47 .065" 40.0 49.0 44.11 .070" 62.3 71.7 66.35 .075" 101 111 107.5 .080" 13.5 21.7 17.93 .065" 22.7 30.0 27.00 .065"	27.0       32.0       29.14       .065"       20         42.8       48.7       45.19       .070"       18         49.5       64.7       54.72       .075"       16         95.0       100       98.51       .080"       14         35.0       42.4       39.36       .075"       18         18.7       26.0       22.09       .065"       22         22.2       28.7       26.47       .065"       20         40.0       49.0       44.11       .070"       18         62.3       71.7       66.35       .075"       16         101       111       107.5       .080"       14         13.5       21.7       17.93       .065"       22         22.7       30.0       27.00       .065"       20	27.0       32.0       29.14       .065"       20       16         42.8       48.7       45.19       .070"       18       20         49.5       64.7       54.72       .075"       16       30         95.0       100       98.51       .080"       14       60         35.0       42.4       39.36       .075"       18       20         18.7       26.0       22.09       .065"       22       10         22.2       28.7       26.47       .065"       20       16         40.0       49.0       44.11       .070"       18       20         62.3       71.7       66.35       .075"       16       30         101       111       107.5       .080"       14       60         13.5       21.7       17.93       .065"       22       10         22.7       30.0       27.00       .065"       20       16

## 2.8 Pull Out (Insulation Crimp Tensile) - Group 12

All samples met the minimum specified requirement for Pull Out (Insulation Crimp Tensile), in accordance with the specification.

Tensile in Pounds

Part No.	Min.	Max.	Mean	Crimp Ht.	AWG	Min. Req.
Part No.  2-520401-2 2-520401-2 2-520401-2 3-520402-2 3-520402-2 2-520405-2 2-520405-2 2-520406-2 3-520406-2	Min. 5.7 4.2 5.6 4.6 5.5 3.8 4.2 3.4 3.6 3.2 6.2	Max. 6.9 5.3 6.6 7.0 9.5 5.4 6.9 4.5 6.8 9.2	Mean 6.39 4.85 6.05 5.33 7.22 4.39 5.81 3.94 4.09 5.29 7.29	Crimp Ht.  .065" .070" .075" .080" .075" .065" .065" .075" .080"	AWG 22 20 18 16 14 18 22 20 18 16 14	Min. Req.  3.0 lbs.
3-520406-2 2-520932-2 2-520932-2	6.2 1.7 2.0	9.2 3.2 3.6	7.29 2.42 2.84	.080" .065" .070"	14 22 18	3.0 lbs. 1.0 lb. 1.0 lb.

## 2.9 Secureness of Insulation (Unassembled) - Groups 7 & 9

There was no separation of insulation from the terminal bodies as a result of Secureness of Insulation (Unassembled) testing.

## 2.10 Secureness of Insulation (Assembled) - Groups 8. 10, & 11

There was no separation of insulation from the terminal bodies as a result of Secureness of Insulation (Assembled) testing.

### 2.11 Engagement & Disengagement - Group 13

All samples met the minimum and maximum force requirements, as specified in Figure 2.

		Force, pounds								
Tab Size Terminal — Plain Plating Brass	1st Insertion	19	t Withdra	wal	6th Withdrawa					
	Individual Maximum	indv., max.	Average minimum	Indv., minimum	Average minimum	Indv., minimum				
.250	Tin	17	17	5	3	4	3			
.187	Tin	15	20	5	3	3	2			
.110	Tin	12	14	3	2	2	1			

Figure 2

#### All Forces in Pounds

	Tab	<u>lst</u> Insert.	lst	Withdr	awal	6th Witl	ndrawal
Part No.	Size	Max.	Max.	Avg.	Min.	Āvg.	Min.
2-520401-2 3-520402-2 2-520405-2 3-520406-2 2-520932-2	187 187 250 250 110	8.7 8.0 9.8 11.3 6.8	9.8 8.5 10.8 12.0 6.5	6.5 6.5 8.1 10.3	4.0 5.5 5.3 6.3 3.5	10.6 12.0 9.7 11.2 6.0	4.8 9.5 5.5 8.3 4.0

## 2.12 Flex Insulation Crimp - Group 2

All samples met the flex insulation test requirement. There was no insulation disengaging from the insulation crimp on any samples tested.

### 2.13 Heat Age, 136°C - Groups 3, 9, & 10

There was no evidence of physical damage to any receptacles, as a result of exposure to a temperature of 136°C for 7 days.

## 2.14 Heat Age/Humidity - Groups 4 & 11

There was no evidence of physical damage to any receptacles, as a result of exposure to a temperature of 100°C for 7 days, followed by a steady state humidity for 24 hours. Samples from Group 4 met the Dielectric Withstanding, Test Condition A requirement, and samples from Group 11 met the Secureness of Insulation (Assembled) requirement.

#### Test Methods

## 3.1 Examination of Product - Groups 1 thru 13

The product drawings and inspection plans were used to examine the samples. They were examined visually and functionally.

# 3.2 Dielectric Withstanding, Test Condition A - Groups 2, 3, and 4

Assembled terminals were subjected to a dielectric withstanding voltage, in accordance with Test Condition A of UL310. With the tab entry section of each sample sealed with dielectric wax, the sample was embedded vertically in #12 lead shot, so that only the portion of the outer insulating surface that covers live parts is to be covered with lead shot. A test potential of 3.4 kv ac was applied, at a rate of 500 volts per second, between the lead shot and the end of the assembled wire. This potential was applied for one minute. The voltage was then returned to zero. This test was not performed on Series 110 contacts for Groups 3 and 4.

# 3.3 Dielectric Withstanding, Test Condition C - Group 5

Unassembled terminals were subjected to a dielectric withstanding voltage, in accordance with Test Condition C of UL310. Each unwired sample was mated with a receptacle tab, and the crimp end of the sample was mounted vertically on a flat metal plate. A test potential of 3.0 kv ac was applied, at a rate of 500 volts per second, between the plate and the receptacle tab. This voltage was applied for one minute. The voltage was then returned to zero. This test was not performed on Series 110 contacts.

# 3.4 Dielectric Withstanding, Tab Receptacle Entry Position - Group 6

The tab receptacle entry section of each wired terminal was mounted vertically on a flat metal plate. A test potential of 1.0 kv ac was then applied, at a rate of 500 volts per second, between the wire end of the assembled terminals and the metal plate. This potential was applied for one minute. The voltage was then returned to zero. This test was not performed on Series 110 Ultra-Fast Plus Receptacles.

# 3.5 Heating (Temperature Rise) - Group 1

The wired terminals were mounted on fixture boards, as specified in NEMA DC2. The terminals were energized at the specified current, and the receptacle temperature was measured. Thermocouples were attached to the receptacles to measure the temperature, as shown in Figure 3 below. This temperature was then subtracted from the ambient temperature to find the temperature rise. When three readings at five minute intervals were the same, the temperature was recorded.

# 3.6 Heat Cycling (Current Cycle) - Group 1

The wired terminals were mounted on fixture boards, as specified in NEMA DC2 and UL310. The samples were then subjected to 500 cycles of current cycling. With each cycle consisting of current ON for 45 minutes and current OFF for 15 minutes, there were millivolt drop readings and t-rise readings measured initially, at the 24th cycle, and at the 500th cycle at points shown in Figure 3 below. The temperature rise measurements were recorded with ac applied, while voltage drop measurements were recorded with dc applied.




Figure 3

### 3.7 Pull Out (Wire Crimp Tensile) - Group 2

The minimum axial load, specified for each wire size, was applied to each sample for a one-minute hold period. This load was applied at a rate of one inch per minute. After the one-minute hold period, each sample was pulled to failure.

## 3.8 Pull Out (Insulation Crimp Tensile) - Group 12

Testing was performed on receptacles with only the wire insulation section crimped on each sample. (The wire was not in the crimp barrel for this test.) An axial load was applied to each sample, at a rate of one inch per minute. Twenty samples of each wire size and terminal type were tested, except on Series 110 Receptacles, where only minimum and maximum wire applications were tested. Testing was performed on single wire applications only.

# 3.9 Secureness of Insulation (Unassembled) - Groups 7 & 9

Samples were suspended vertically from a mating tab, which was inserted into each receptacle. A 3.0 pound weight was applied to the insulation at the wire crimp end of each terminal for a one-minute hold period.

# 3.10 Secureness of Insulation (Assembled) - Groups 8, 10, & 11

Samples were suspended vertically from a slotted plate fixture, which allowed an axial load to be applied to the crimped end of the terminal insulation. A 6.0 pound load was then gradually applied, at a rate of approximately 1.0 pound per second, to the receptacle end of each sample. The load was held for one minute, when the required force was reached.

# 3.11 Engagement & Disengagement - Group 13

Samples from Group 13 were subjected to engagement & disengagement testing. Each receptacle was mounted horizontally in a force actuation fixture. This fixture was equipped with a device used to measure engagement and disengagement forces. The specified mating tab for each receptacle was used for these measurements. Each receptacle and tab was engaged and disengaged 6 times, while forces were recorded.

## 3.12 Flex Insulation Crimp - Group 2

Flex Insulation testing was performed on all samples of Group 2. Each sample wire was subjected to four 90° flexures, in relation to the terminal, when mounted in a vertical plane. Flexing was performed in four directions, at 90° apart from each other. The holding point for the sample wire was a distance 5 times the diameter of the wire insulation from the wire crimp insulation.

## 3.13 Heat Age, 136°C - Groups 3, 9, & 10

All samples in Groups 3, 9 and 10 were subjected to Heat Aging. The samples were subjected to 7 days of exposure to a temperature of 136°C. After conditioning, all samples in Groups 3, 9 and 10 were subjected to Dielectric Withstanding Voltage, Test Condition A, Secureness of Insulation (Unassembled) and Secureness of Insulation (Assembled), respectively.

## 3.14 Heat Age/Humidity - Groups 4 & 11

All samples in Groups 4 and 11 were subjected to 100°C for 7 days, followed by 85% R.H. at 30°C for 24 hours. After conditioning, each sample was crimped to appropriate size wire, and the samples in Groups 4 and 11 were subjected to Dielectric Withstanding Voltage, Test Condition A, and Secureness of Insulation (Assembled), respectively.

#### 3. **Validation**

Report prepared by,

James A. D'Angelo

Engineering Assistant Product Testing Section Corporate Test Laboratory

dryllo -13,89

Reviewed by,

Richard A. Groft

Supervisor, Design Assurance Testing

Product Testing Section Corporate Test Laboratory <u> 5 /30 /89</u>

Approved by,

William Zelner

Manager, Product Assurance

Automotive/Consumer Business Group

6/19/89